


Mini Data Center Solutions

Mini Data Center Server Rack with Integrated Side Cooler DX or Water Based



CERTIFIED

All in One
Compact Data Center

Highlights :

- Integrated monitoring system
- Install Data Center where you want and need it
- Rapid deployment in 4-6 weeks from plan to start-up
- Low total cost of ownership
- Up to 50% less space required
- No raised floor required
- Full turnkey Data Center including cooling, structured cabling, monitoring,
- Power management and protection
- Scalable from 1 rack to hundreds of racks
- Standalone Data Center
- Individual rack cooling up to 30 kW
- High level security within rack fire protection and monitoring systems
- Advanced power management with IP PDU and UPS systems
- Internal redundancy achieved by using 3x fans.
- External redundancy achieved by using N+1 side coolers
- Structured cabling solutions with overhead cable channels
- Access Control options with either keypad, RFID card reader or fingerprint reader to open the cabinet doors

Applications:


- High density servers exceeding 10 Kw
- Mobile Containers/Shelters
- Branch Offices
- Disaster recovery operations
- Small clinics/hospitals
- Warehouses
- Remote installations
- Temporary installation
- Mobile applications



| | Air cooled(DX) Side Cooler | Water Based Side Cooler |
|------------------|----------------------------|-------------------------|
| Cooling Capacity | 28 kW | 30 kW |
| Rack Height | 42U/47U | 42U/47U |



Chiller Unit



Outdoor DX Unit

Mini Data Center Solutions

Components of the Mini Data Center

